

Project: FLORENCE COUNTY EMS
[BID NO. 31-14/15]

Addendum No.: TWO

Date: June 12, 2015

THE FOLLOWING INFORMATION SHALL BE ADDED TO THE CONTRACT DOCUMENTS:

A. ARCHITECTURAL

1. Refer to sheet A0.0-2 and Wall Type E3.
 - a. At contractor's option, 3 5/8-inch metal stud (18 gauge) may be used in lieu of 6 inch metal stud (18 gauge) at this wall type.

B. ELECTRICAL

1. The lighting package as submitted for prior approval by R L Miller Co (Greer, SC), will be approved with the following exceptions as noted by the electrical engineer, Optima Engineering:
 - a. A5 – Provide (3)-F28T8 lamps with (1) 1x32t8 ballast and (2) 2x32t8 ballast.
 - b. A5EM - Provide (1) 1x32t8 ballast and (2) 2x32t8 ballast.
 - c. HB3 – Provide (3) 2x54THHO Ballast
 - d. HB3EM – Provide (3) 2x54THHO Ballast

END OF ADDENDUM No. 2