



Florence County Government
Procurement Department

July 27, 2015

**ADDENDUM NO.1- 2015 CPST II RESURFACING PROJECT
PACKAGE 4: DISTRICT 9 (BID NO. 04-15/16)**

One question is address in this addendum. The answer is highlighted in **BOLD RED and UNDERLINED.**

Question: The bid tab included in the package lists items such as Permanent Construction signs (Ground Mounted), 6" White solid Lines for Crosswalk, Permanent Yellow Pavement Markers Bi-Dir – 4"X4" & Concrete curb & Gutter (1' – 6") OGEE. There are no quantities shown for these items. Am I correct that these are not actual bid items for this project?

Answer: If a bid item has no quantities then we do not anticipate these items on the project and they can be excluded from the bid. You only need to provide costs for items that have quantities.

Also, a revised bid sheet and map are attached. Use the revised bid sheet as the basis for your bid. The revised sheet includes the addition of Farm Quarters Rd to the bid sheet.

YOU MUST ACKNOWLEDGE THIS ADDENDUM BY SIGNING BELOW AND SUBMITTING IT WITH YOUR BID.

I have read and acknowledged this addendum for bid no. 04-15/16.

Authorized Signature

Printed Name

Date

Company Name

2015 FLORENCE COUNTY RESURFACING PROJECT PACKAGE 4 (DISTRICT 9)
BID TAB
ADDENDUM 1

CPST PROJECT NO.			LENGTH (FT.) LENGTH (MI.)	2700 0.51	1200 0.23	305 0.06	620 0.12	750 0.14	850 0.16
			437	438	439	440	441	442	
BAMS #	DESCRIPTION	UNITS	CLAUDE DOUGLAS CIR	HEPBORN BLVD	ASHWOOD LN	ASPEN ST	DUNWOODY RD	EVERGREEN RD	
1031000	MOBILIZATION	LS	NEC.	NEC.	NEC.	NEC.	NEC.	NEC.	
1071000	TRAFFIC CONTROL	LS	NEC.	NEC.	NEC.	NEC.	NEC.	NEC.	
4011004	LIQUID ASPHALT BINDER PF64-22	TON	30.000	14.000	5.000	8.000	10.000	12.000	
4012060	FULL DEPTH ASPHALT PAVEMENT PATCHING (6" UNIF.)	SY	50.000	50.000	10.000	10.000	50.000	10.000	
4013990	MILLING EXISTING ASPHALT PAVEMENT (VARIABLE)	SY	3710.000	2130.000	514.000	910.000	1100.000	1250.000	
4030340	HOT MIX ASPHALT SURFACE COURSE - TYPE C	TON	495.000	237.000	70.000	136.000	165.000	187.000	
6051120	PERMANENT CONSTRUCTION SIGNS (GROUND MOUNTED)	SF							
6250012	6" WHITE SOLID LINE FOR CROSSWALK	LF							
6301100	PERMANENT YELLOW PAVEMENT MARKERS BI-DIR.- 4"X4"	EA							
7197110	ADJUST DROP INLET	EA							
7203130	CONCRETE CURB AND GUTTER(1'-6") OGEE	LF							
	Total								

2015 FLORENCE COUNTY RESURFACING PROJECT PACKAGE 4 (DISTRICT 9)
BID TAB
ADDENDUM 1

			LENGTH (FT.) LENGTH (MI.)	670 0.13	1200 0.23	1000 0.19	680 0.13	860 0.16	2740 0.52
CPST PROJECT NO.			443	444/445	446	447	385	386	
BAMS #	DESCRIPTION	UNITS	PERIWINKLE LN	FARMWOOD DR	HEATHER DR	PATRICK DR	ALBERMARLE BLVD.	BANBURY CIR	
1031000	MOBILIZATION	LS	NEC.	NEC.	NEC.	NEC.	NEC.	NEC.	
1071000	TRAFFIC CONTROL	LS	NEC.	NEC.	NEC.	NEC.	NEC.	NEC.	
4011004	LIQUID ASPHALT BINDER PF64-22	TON	9.000	16.000	13.000	9.000	6.000	30.000	
4012060	FULL DEPTH ASPHALT PAVEMENT PATCHING (6" UNIF.)	SY	10.000	0.000	0.000	0.000		45.000	
4013990	MILLING EXISTING ASPHALT PAVEMENT (VARIABLE)	SY	982.000	0.000	0.000	0.000			
4030340	HOT MIX ASPHALT SURFACE COURSE - TYPE C	TON	147.000	264.000	220.000	150.000	95.000	502.000	
6051120	PERMANENT CONSTRUCTION SIGNS (GROUND MOUNTED)	SF							
6250012	6" WHITE SOLID LINE FOR CROSSWALK	LF							
6301100	PERMANENT YELLOW PAVEMENT MARKERS BI-DIR.- 4"X4"	EA							
7197110	ADJUST DROP INLET	EA							
7203130	CONCRETE CURB AND GUTTER(1'-6") OGEE	LF							
	Total								

2015 FLORENCE COUNTY RESURFACING PROJECT PACKAGE 4 (DISTRICT 9)
BID TAB
ADDENDUM 1

			LENGTH (FT.) LENGTH (MI.)	1280 0.24	560 0.11	2000 0.38	700 0.13	5960 1.13	145 0.03
CPST PROJECT NO.			387	388	389	390	470	402	
BAMS #	DESCRIPTION	UNITS	BEDFORD LN	MILFORD LN	S ARUNDEL DR	ST JAMES LN	WHITEHALL CIR	ALABAMA LN	
1031000	MOBILIZATION	LS	NEC.	NEC.	NEC.	NEC.	NEC.	NEC.	
1071000	TRAFFIC CONTROL	LS	NEC.	NEC.	NEC.	NEC.	NEC.	NEC.	
4011004	LIQUID ASPHALT BINDER PF64-22	TON	16.000	6.000	25.000	8.000	72.000	2.000	
4012060	FULL DEPTH ASPHALT PAVEMENT PATCHING (6" UNIF.)	SY	165.000				165.000	0.000	
4013990	MILLING EXISTING ASPHALT PAVEMENT (VARIABLE)	SY						0.000	
4030340	HOT MIX ASPHALT SURFACE COURSE - TYPE C	TON	258.000	103.000	410.000	128.000	1202.000	32.000	
6051120	PERMANENT CONSTRUCTION SIGNS (GROUND MOUNTED)	SF							
6250012	6" WHITE SOLID LINE FOR CROSSWALK	LF							
6301100	PERMANENT YELLOW PAVEMENT MARKERS BI-DIR.- 4"X4"	EA							
7197110	ADJUST DROP INLET	EA							
7203130	CONCRETE CURB AND GUTTER(1'-6") OGEE	LF							
	Total								

2015 FLORENCE COUNTY RESURFACING PROJECT PACKAGE 4 (DISTRICT 9)
BID TAB
ADDENDUM 1

			LENGTH (FT.) LENGTH (MI.)	215 0.04	500 0.09	1120 0.21	150 0.03	220 0.04	1000 0.19
CPST PROJECT NO.			403	404	405	406	407	408	
BAMS #	DESCRIPTION	UNITS	ARIZONA WAY	CALIFORNIA RD	FLORIDA DR	GEORGIA CT	LOUISIANA LN	OAK FOREST BLVD	
1031000	MOBILIZATION	LS	NEC.	NEC.	NEC.	NEC.	NEC.	NEC.	
1071000	TRAFFIC CONTROL	LS	NEC.	NEC.	NEC.	NEC.	NEC.	NEC.	
4011004	LIQUID ASPHALT BINDER PF64-22	TON	4.000	7.000	17.000	3.000	4.000	15.000	
4012060	FULL DEPTH ASPHALT PAVEMENT PATCHING (6" UNIF.)	SY	30.000	0.000	0.000	25.000	0.000		
4013990	MILLING EXISTING ASPHALT PAVEMENT (VARIABLE)	SY		0.000					
4030340	HOT MIX ASPHALT SURFACE COURSE - TYPE C	TON	55.000	115.000	277.000	39.000	56.000	238.000	
6051120	PERMANENT CONSTRUCTION SIGNS (GROUND MOUNTED)	SF							
6250012	6" WHITE SOLID LINE FOR CROSSWALK	LF							
6301100	PERMANENT YELLOW PAVEMENT MARKERS BI-DIR.- 4"X4"	EA							
7197110	ADJUST DROP INLET	EA		4.000	8.000		1.000	1.000	
7203130	CONCRETE CURB AND GUTTER(1'-6") OGEE	LF							
	Total								

			LENGTH (FT.)	275	850	215	2000		
			LENGTH (MI.)	0.05	0.16	0.04	0.38	5.83	
CPST PROJECT NO.			409	410	411	424			
BAMS #	DESCRIPTION	UNITS	TENNESSEE TER	TEXAS RD	UTAH CT	FARM QUARTER RD	TOTAL PROJECT QUANTITY	UNIT PRICE	TOTAL PRICE
1031000	MOBILIZATION	LS	NEC.	NEC.	NEC.	NEC.	NEC.	NEC.	
1071000	TRAFFIC CONTROL	LS	NEC.	NEC.	NEC.	NEC.	NEC.	NEC.	
4011004	LIQUID ASPHALT BINDER PF64-22	TON	4.000	11.000	4.000	12.000	372.000		
4012060	FULL DEPTH ASPHALT PAVEMENT PATCHING (6" UNIF.)	SY		30.000	10.000	100.000	760.000		
4013990	MILLING EXISTING ASPHALT PAVEMENT (VARIABLE)	SY					10596.000		
4030340	HOT MIX ASPHALT SURFACE COURSE - TYPE C	TON	61.000	171.000	55.000	202.000	6070.000		
6051120	PERMANENT CONSTRUCTION SIGNS (GROUND MOUNTED)	SF					0.000		
6250012	6" WHITE SOLID LINE FOR CROSSWALK	LF					0.000		
6301100	PERMANENT YELLOW PAVEMENT MARKERS BI-DIR.- 4"X4"	EA					0.000		
7197110	ADJUST DROP INLET	EA					14.000		
7203130	CONCRETE CURB AND GUTTER(1'-6") OGEE	LF					0.000		
							0.000		
							0.000		
							0.000		
	Total							TOTAL	

Florence County 2015 Resurfacing Project Package 4

Area Map- FARM QUARTER RD. (DISTRICT 9)

ADDENDUM – 1 MAP

